

CLIENT: GUYANA POWER AND LIGHT INC.

PROJECT: REPAIRS TO CUSTOMER SERVICE AREA OF GROUND FLOOR, MAIN BUILDING AT MAIN STREET, GEORGETOWN



**SUMMARY OF BILLS**

BILL No.	DESCRIPTION	AMOUNT
1	PRELIMINARIES	
2	RENOVATION WORKS	
	<b>SUB TOTAL</b>	
	Contingency (10% of Sub-Total)	
<b>GRAND TOTAL TO FORM TENDER</b>		

CLIENT: GUYANA POWER AND LIGHT INC.

PROJECT: REPAIRS TO CUSTOMER SERVICE AREA OF GROUND FLOOR, MAIN BUILDING  
AT MAIN STREET, GEORGETOWN



**BILL No.1: PRELIMINARIES**

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1.1	Provide the means of access to site and mobilize equipment, plant and personnel including any necessary facilities for contractor personnel and demobilize same at the completion of the works	Sum			
1.2	Provide for protection of the works	Sum			
<b>BILL NO. 1 - TOTAL CARRIED TO SUMMARY</b>					

CLIENT: GUYANA POWER AND LIGHT INC.

PROJECT: REPAIRS TO CUSTOMER SERVICE AREA OF GROUND FLOOR, MAIN BUILDING AT MAIN STREET, GEORGETOWN



BILL No.2: RENOVATION WORKS

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<i>Note: All members are to be prefabricated and will only be installed on site, no construction is catered for on site. Timber members will be joined using drywall screws and adhesive, nails would not be accepted.</i>				
	<u>Queries and New Service Area</u>				
2.1	Provide for the demolition of existing counters and defective partition walls to the southern and western side of the existing building as directed by the Engineer. The approximate length of the existing counters are: 12', 29' and 16'.	Sum	...		
2.2	Supply and install 2" x 4" Pinewood Timber members to construct frame for counters and drawers. The dimensions are as follows: 12' 5" long x 36" wide x 30" high (to top of counter) and 26' long x 36" wide x 30" high.	Bm	176		
2.3	Provide for the installation of recessed decorative laminated modesty panels rock for exterior wall below counter and interior walls also including drawers separators. Rate to cater for screws to secure same to timber frame.	Sq.yd	28		
2.4	Supply and install 1" x 6" dressed GH as foot stop to bottom of exterior wall where laminated modesty panels are installed.	Bm	20		
2.5	Provide for the installation of prefabricated cubicle walls measuring 4' wide x 6' 6" high each, to both end of a 12' 3" long granite counter and to separate 6 nr cubicles for the new service section (26' counter) @ 3' 6" ctrs, same must be constructed using modern and durable metal frame with plexi panel. Rate to cater for securing same to floor. (12 Pcs)	Sq.yd	35		
2.6	Provide for the installation of prefabricated cubicle walls measuring: 4' 6" high for supervisors, same must be upholstered with padded sections, top panels will be transparent using 3/8" thk. perspex. Rate to cater for securing same to floor. And size will cater for a guest chair as shown in drawing.	Sq.yd	20		
2.7	Provide for the construction of upholstered panel door, same as walls measuring:30" wide x 4' 6" high. Rate must cater for fly butts to same.	Nr	3		
2.8	Provide for the installation of 36" wide x 3/4" thk. Granite for counter with bullnose finish to all edges of granite. All seams are to be sealed with epoxy, colour must be same/similar to granite colour with the thorough cleaning off of all excess. (two separate counters: 12' 3" long and 26' long)	Ln.ft	28.25		
2.9	Supply and install mobile metal three (3) drawers pedestals with lock and handles measuring: 15" wide x 28" height x 20" depth. Same will be installed to the right side of each partition from ground to counter level same will be used as a support to the granite counter.	Nr	10		
2.10	Supply and install 2" x 2" hollow section metal to construct frame for separation walls, same must allow for the installation of 3/8" thk. Perspex. Rate to include for the application of anti-corrosive paint to same and all bolts and screws as required.	Ln.ft	151		
<b>BILL No. 2 - TOTAL CARRIED FORWARD</b>					



CLIENT: GUYANA POWER AND LIGHT INC.

PROJECT: REPAIRS TO CUSTOMER SERVICE AREA OF GROUND FLOOR, MAIN BUILDING AT MAIN STREET, GEORGETOWN



BILL No.2: RENOVATION WORKS

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
<b>Total Brought Forward</b>					
2.11	Supply and install 3/4" thk. Perspex to 2" x 2" metal frame. Same must cater for 4" dia. Communication opening. Perspex will be installed 10" above counter top to allow for hand passage.	Sq.yd	14		
2.12	Provide for the installation of vision Panel (see through glass at the top) white pine door measuring: 28" wide x 6' 4" high. Rate must include for door frame, hinges, cylindrical lock, door handle and painting.	Nr	1		
2.13	Provide for the installation of internal raceway with PVC grommets for electrical and data cables.	Ln.ft	150		
2.14	Provide for the application of one (1) prime coat and two (2) finishing coats of oil paint to all timber members.	Sq.yd	30		
<b>Manager and Commercial Officer Area</b>					
2.15	Provide for the demolition of existing partition walls. The approximate size is as follows: 80' long x 7' 6" high, including four (4) doors.	Sum	...		
2.16	Provide for the installation of prefabricated cubicle wall measuring: 7' 8" wide x 6' 6" high to area between last cubicle and commercial officer's office wall. Same must be upholstered with padded sections. Rate to cater for securing same to floor and ceiling.	Sq.yd	5.5		
2.17	Provide for the installation of prefabricated cubicle walls measuring: 21' 8" wide x 9' 10" high (to touch existing ceiling. Same must be upholstered with padded sections. One section must include 3/8" thk. Tinted perspex to allow for manager and commercial officer to see general open area to east of their offices. Rate to cater for securing same to floor and ceiling.	Sq.yd	24		
2.18	Provide for the installation of prefabricated cubicle walls to other sides of offices as shown in drawing measuring: 5' 8" wide x 9' 10" high to ends and middle of area and 24' 6" long x 8' high to the front. Same must be upholstered with padded sections. Rate to cater for securing same to floor and ceiling.	Sq.yd	56		
2.19	Provide for the installation of vision Panel (see through glass at the top) white pine door measuring: 32" wide x 6' 8" high. Rate must include for door frame, hinges, cylindrical lock, door handle and painting.	Nr	4		
2.20	Provide for the installation of internal raceway with PVC grommets for electrical and data cables.	Ln.ft	75		
<b>BILL No. 2 - TOTAL CARRIED TO SUMMARY</b>					